Dart Aerospace Ltd. Thursday, 19/03/2009 4:30:43 PM ■ Date User: Julie Dawson **Process Sheet** Customer : CU-DAR001 Dart Helicopters Services **Drawing Name** : STA 84 BRACKET Job Number : 46611 **Estimate Number** : 11035 P.O. Number : D28032 **Part Number** This Issue : 19/03/2009 S.O. No. : : D2803 REV B **Drawing Number** Prsht Rev. : NC **Project Number** : N/A First Issue : // ; B Type : MACHINED PARTS **Drawing Revision** : 46436 **Previous Run** Material : 31/03/2009 Qty: 10 Um: **Due Date** Written By Checked & Approved By Comment 00.11.06 New Issue EC . Est Rev:B Blanks now cut on Waterjet 06-06-14 JLM Est Rev:C Removed Tumbling 08-09-10 JLM Verified By:EC **Additional Product** Job Number: Seq. #: **Machine Or Operation:** Description: 1.0 M6061T6B0500X10000 6061-T6 Bar .500 x 10.00 of WAT. Comment: Qty.: 2.0125 f(s)/Unit Total: 20.1254 f(s) 6061-T6 Bar .50" x 10.0" Material: 6061-T6 bar 10.00" x 0.50" 2.0 WATER JET Comment: FLOW WATER JET 1-Cut as per Template DT8533 Dwg Rev: Prog Rev: 2-Deburr if necessary 3.0 HAAS1 HAAS CNC VERTICAL MACHINING #1 Comment: HAAS CNC VERTICAL MACHINING #1 Machine as per folio FA102 4.0 QC2 INSPECT PARTS AS THEY COME OFF MACHINE

SECOND CHECK

5.0

QC8

Comment: SECOND CHECK

Comment: INSPECT PARTS AS THEY COME OFF MACHINE

Each

Dart Ae	rospace	Ltd						
W/O:			WO	RK ORDER CHANGE	ES			-
DATE	STEP	PR	OCEDURE CHAN	GE	Ву	Date Qty	Approval Chief Eng / Prod Mgr	Approva QC Inspector
		:						
Part No	):	PAR #:	Fault Categ	ory:	NCR: Yes	No <b>DQA</b> :	Date: _	
		esolution:						
NCR:			WORK ORDE	R NON-CONFORMA	NCE (NCR	)		
D.4.T.F.	0===	Description of NC	0	Corrective Action Section	n B	Verification	Annuarial	<b>A</b>
DATE	STEP	Section A	Initial Chief Eng	Action Description Chief Eng	Sign & Date	Section C	Approval Chief Eng	Approval QC inspecto

DATE		Description of NC		Corrective Action Section B		Verification	Ammunual	A
DATE	STEP	Section A	<b>Initial</b> Chief Eng	Action Description Chief Eng	Sign & Date	Section C	Approval Chief Eng	Approval QC inspector

NOTE: Date & initial all entries

Date: Thursday, 19/03/2009 4:30:43 PM User: Julie Dawson **Process Sheet** Customer: CU-DAR001 Dart Helicopters Services Drawing Name: STA 84 BRACKET Job Number: 46611 Part Number: D28032 Job Number: Seq. #: **Machine Or Operation: Description:** 6.0 HAND FINISHING1 HAND FINISHING RESOURCE #1 Comment: HAND FINISHING RESOURCE #1 Chemical Conversion Coat as per QSI 005 4.1 7.0 PACKAGING 1 PACKAGING RESOURCE #1 Comment: PACKAGING RESOURCE #1 Identify and Stock Location: [48 QC21 8.0 FINAL INSPECT Comment: FINAL INSPECTION/W/O RELEASE Job Completion u Bround

## **Dart Aerospace Ltd** W/O: **WORK ORDER CHANGES Approval** Approval DATE STEP PROCEDURE CHANGE By Qty Date Chief Eng / Prod Mgr QC Inspector Part No: \_\_\_\_\_\_ PAR #: \_\_\_\_ Fault Category: \_\_\_\_\_ NCR: Yes No DQA: \_\_\_\_ Date: \_\_\_\_ Resolution: \_\_\_\_\_ Disposition: \_\_\_\_\_ QA: N/C Closed: \_\_\_\_ Date: \_\_\_\_ WORK ORDER NON-CONFORMANCE (NCR) NCR:

		Description of NC		Corrective Action Section B		Varification			
DATE	STEP	Section A	Initial Chief Eng	Action Description Chief Eng	Sign & Date	Verification Section C	Approval Chief Eng	Appr QC Ins	roval spector
		•							
									•
					:		1		

NOTE: Date & initial all entries

DART AEROSPACE LTD	Work Order: ☐ (()()
Description: Bracket	Part Number: D2803-2
Inspection Dwg: D2803 Rev: B	Page 1 of 1

## FIRST ARTICLE INSPECTION CHECKLIST

X First Article Prototype


Drawing Dimension	Tolerance	Actual Dimension	Accept	Reject	Method of Inspection	Comments
Ø0.757	+0.005/-0.000	00.759	V			
1.420	+/-0.001	1.420	1			
Ø0.191	+0.005/-0.000	Ø 0.193	<b>V</b>			
Ø0.507	+0.000/-0.001	80.5060	V			
Ø0.507 x 0.250	+0.000/-0.001		<b>✓</b>			
12.411	+/-0.010	12.411	V			
6.933	+/-0.010	6.933	<b>/</b>			<del></del>
0.250	+/-0.010	0.25	V			
0.875	+0.000/-0.001	0.8750	<b>✓</b>			
0.250	+0.000/-0.005	0.248	/			
0.125	+/-0.010	0.126	<b>✓</b>			
0.125	+/-0.010	0.128	/			
0.500	+/-0.010	0.491	<b>V</b>			
0.125	+/-0.010	0.128	<b>✓</b>			
0.188	+/-0.010	0.188	<b>✓</b>			
0.562	+/-0.010	0.563	<b>✓</b>			
0.125	+/-0.010	0.126	/			
			-			
			*	-		

Measured by:	H.A	Audited by:	and	Prototype Approval:	N/A
Date:	09/04/10	Date:	09/04/13	Date:	N/A

Rev	Date	Change	Revised by	Approved
Α	05.04.25	New Issue	KJ/JLM	
В	06.12.07	13.558 dimension removed	KJ/JLM , ,	
С	08.01.16	Tolerance revised for 0.875 dimension	KJ/EC/DD	<u> </u>
			<del></del>	



DESIGI	CP	DRAWN BY	DART AEROSPA HAWKESBURY, ONTARIO,	
CHECK	(ED M	APPROVED M	DRAWING NO.	REV. B
	卅	#	D2803	SHEET 1 OF 2
DATE	······	***************************************	TITLE	SCALE
 04.1	1.22		STA 84 BRACKET	1:3
Α		00.11.07	NEW ISSUE	



D2803-1 BRACKET (SHOWN). D2803-2 BRACKET (OPPOSITE)

1) MACHINE PER DRAWING FILE "D2803.SLDPRT"

2) MATERIAL: 6061-T6 (QQ-A-200/8) OR (QQ-A-250/11) 0.500 THICK NOTICE

3) DEBURR TO LEAVE RO.030 - 0.063 ON ALL EDGES

4) FINISH: CHEMICAL CONVERSION COAT PER DART QSI 005 4.1

5) TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED

**SHOP COPY** 

**RETURN TO** 

**ENGINEERING** 

UNCONTROLLED COPY


SUBJECT TO AMENDMENT

Copyright @ 2000 by DART AEROSPACE LTD

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.



DESIGN CP	DRAWN BY	DART AEROS HAWKESBURY, ONT	
CHECKED	APPROVED	DRAWING NO.	REV. B
林	4-	D2803	SHEET 2 OF 2
DATE		TITLE	SCALE
04.11.22		STA 84 BRACKET	1:3



## D2803-041/-043 BRACKET ASS'Y (SHOWN). D2803-042/-044 BRACKET ASS'Y (OPPOSITE)

6) FINISH: POWDER COAT ASSEMBLY GLOSS WHITE (4.3.5.1) OR GREY SANDTEX (4.3.5.6) OR BLACK SANDTEX (4.3.5.7) OR GREEN SANDTEX (4.3.5.8) PER DART QSI 005 4.3

Copyright © 2000 by DART AEROSPACE LTD

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.